


DESI Spectrograph: Throughput Measurement

Laurent Le Guillou (UPMC/LPNHE)

*DESI France Workshop
Paris/Saclay, Nov. 17th-18th, 2016*



Julien Coridian (electronics), Patrick Ghislain (mechanics), Julien Guy (scientist),
Sonia Karkar (project engineer), Laurent Le Guillou (scientist), Yann Orain (mechanics),
Philippe Repain (mechanics), Eduardo Sepulveda (electronics)



Dark Energy Spectroscopic Instrument


Talk outline

- **The DESI spectrograph**
- **Throughput Measurement: Motivations & Principle**
- **Flux Calibration Device for the Test Fiber Slit**
 - Mechanical design
 - Photodiode (inter)calibration(s)
- **Installation at Winlight**
 - Integration in the AMU testbench
 - First tests and measurements
- **Next steps...**




The DESI spectrograph


- 10 identical spectrographs
- 10 x 500 fibers
- 3 arms : NIR, Red, Blue




The DESI spectrograph



Illumination Testbench (AMU)




Fiber slit(s): light injection



Fiber slit(s): “sparse fiber slit”

- 21 well separated fibers
- May be illuminated individually (AMU bench)

Fiber : $f/3.57$
Angle $\theta \sim 8^\circ$




Throughput measurement proposal

- **Critical** : Misestimating the spectrograph throughput may endanger the DESI science (and the mistake may be done 10 times!)
- Measurement to be done during **slit removal/reinstall** repeatability test (limited overhead)
- **Calibration of the total flux** at the exit of each fiber of the sparse fiber slit
- **Proposed Procedure** : for the same illumination setups (LEDs)
 - **(1) Sparse Test Slit inside the spectrograph** : integrated flux measured on the CCD for the 3 arms of the spectrograph ;
 - **(2) Sparse Test Slit outside of the spectrograph, in front of our device** : flux (in the same illumination conditions) measured by our calibrated photodiode
- **Ratio (1)/(2)** gives **throughput** (from fiber exit to the CCD included)



Mechanical design



Fiber : $f/3.57$
Angle $\theta \sim 8^\circ$

99 % encl. energy : $f/2.5$
Angle $\theta \sim 11.3^\circ$

Curved rail

$\alpha = 7.42^\circ$ Test Slit Head


Calibrated Photodiode
(DKD/NIST)

mounted on a linear stage
(PI Micos VT-80 150 mm)




Throughput measurement device

Motorized
linear stage
Pi/MICOS
<0.4 μm accuracy




Curved rail
(radius 500 mm)

Calibrated
Photodiode
10x10 mm²



Throughput measurement device

Dedicated
Dark Box



Calibrated
Photodiode

Mock test slit
3D printed
Old fiber bundle
(DESY, H1)




Calibrated Photodiode


- MD-37-SU100 **calibrated (spectral responsivity [A/W])**
 - **DKD (DE) certified absolute calibration**
 - 2 % on 250 – 1100 nm.
- Size : $10 \times 10 = 100 \text{ mm}^2$
- Photodiode current readout : picoammeter
Keithley 6514, or better **6482** (2 channels), (fA)
- **Simultaneous monitoring of :**
 - Light flux in the integrating sphere
 - Light flux exiting the fiber
 - Control of the **illumination stability**




Illumination Testbench (AMU)





Photodiode Calibration (DKD certified)





Photodiode Calibration (DKD certified)



Photodiode Calibration & checks at LPNHE




Photodiode Calibration & checks at LPNHE




Integration on the AMU Testbench


- **Challenging mechanical interface** between the fiber slit and our device (collision with fiber ends should be avoided at all cost!!)
- **Integration within the AMU testbench software** and the ICS (Xavier Regal, AMU)



Integration on the AMU Testbench (dark box)




Installation at Winlight (sept. 2016)




Dark Energy Spectroscopic Instrument

Laurent Le Guillou (UPMC/LPNHE)
DESI France Workshop – Paris/Saclay, Nov 17th-18th, 2016


Installation at Winlight (sept. 2016)



First “scans” by moving the photodiode




Scan of all the sparse slit fibers (S. Royanette)




1 broken fiber; last one unreachable (mechanical limit)



Illumination stability



Integrated in the Spectrograph Tests (AMU)



Conclusions, and next steps

- ◆ Throughput measurement device **built, tested and installed on AMU testbench** at Winlight.
- ◆ On going improvement on the **photodiode current noise**.
- ◆ Needed to complete the throughput measurement:
 - ◆ Pipeline & spectra extraction for LED sources (J. Guy)
 - ◆ A good knowledge of the sensors, esp. the **CCD gains** (NIR, Red, Blue)
 - ◆ Charact. of the neutral densities and spectro. shutter.
- ◆ Cycles of Sparse Slit head **insertion/extraction** to do the measurement (expected early 2017).



LED spectra

